## VIBRO-\COUSTICS® A Swegon Group company

**VISCMA** 


1" (25 mm) / 2" (50 mm) **Deflection ARTR Adjustable Rooftop Isolation Rail** 


**ARTR** 

File No.: DS-ARTR-001 Supersedes: new

Date: 21 Apr 2014 Date: new

tel: 416-291-7371 1-800-565-8401 web: www.vibro-acoustics.com fax: 416-291-8049 1-888-811-2264 eml: info@vibro-acoustics.com





## NOTES

- · Model ARTR rail is a curb-mounted vibration isolation rail with adjustable integral isolators
- 1" (25 mm) or 2" (50 mm) static deflection springs as specified
- Full perimeter neoprene gasket will be supplied loose for field installation
- Rail is constructed from minimum 4" (102 mm) high gauge G90 galvanized steel top channel
- · Special top arrangement with a counter-flashing available for rooftop units that do not have a perimeter base with an overhang

OPTIONS
Duct supports
Flexible duct supports
Knock-down construction for field assembly
Solid top cover
Isolators for pedestal mounting
Seismic and/or wind: include calculations stamped by a PE
Noise control: 2" (50 mm) acoustical barrier framing

Project:	TAG:		UNIT:	
Customer:	DWN:	снк:	REV:	DATE:
Consultant:	COMMENTS:			
V-A Project No.:				
V-A Project Manager:				